BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of Work: Works related to damaged caused due to Flood in ward No. 10 (Doddabommasandra).

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	1069.74	Removing and Resetting of Footpath Slab etc complete as per specifications and directions of engineer in charge of the work	Sqm	235.00	Rupees Two Hundred Thirty Five Only
2	574.16	Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost etc complete as per specifications and directions of engineer in charge of the work	Cum	204.60	Rupees Two Hundred Four and Sixty Paise Only
3	20.10	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:4:8(M5) Using 40 mm nominal size graded crushed coarse aggregates etc complete as per specifications and directions of engineer in charge of the work	Cum	5726.60	Rupees Five Thousand Seven Hundred Twenty Six and Sixty Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
4	79.95	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates etc complete as per specifications and directions of engineer in charge of the work	Cum	6893.04	Rupees Six Thousand Eight Hundred Ninety Three and Four Paise Only
5	3.92	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications etc complete as per specifications and directions of engineer in charge of the work	Tonne	101387.00	Rupees One Hundred One Thousand Three Hundred Eighty Seven Only
6	503.46	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge of the Work.	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
7	72.00	Providing & fixing RCC Precast Cover slab of 230mm thick for drain in cement concrete M20 using graded granite jelly 200mm & down size with steel reinforcement including formwork, lift charges, curing & concrete finished surface both sides etc,. And as per drawing & the direction of Engineer-in-charge	Sqm	5418.00	Rupees Five Thousand Four Hundred Eighteen Only
8	539.71	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum etc complete as per specifications and directions of engineer in charge of the work	Cum	81.40	Rupees Eighty One and Forty Paise Only
9	6770.03	Cost of Haulage Excluding Loading and Unloading, Case-1 : Surfaced Road A Taking output 10 t load and lead 10 km = 100 t.km etc complete as per specifications and directions of engineer in charge of the work	T.kms	12.00	Rupees Twelve Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
10	2190.00	Providing and Fixing Steel Work in built up tubular (round rectangular hollowtube etc) truseses etc, including cutting, hoisting, fixing in postion and applying priming coat of approved steel primer including welding and bolted with Special shaped washer set complete electric resistance ordiction butt weleded tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of Engineer in Charge	Kgs	121.00	Rupees One Hundred Twenty One Only

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Executive Engineer
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
Byatarayanapura Division
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
BBMP, Bangalore - 92
ಬೃ.ಬೆಂ.ಮ.ಪಾ., ಬೆಂಗಳೂರು

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))